PriceLess Amp Restoration Bassman Restoration Estimate

Parts:

Tubes	Quantity	Cost	Sub Total
Matched Pair Svetlana 6L6GC	1	$ 38.00	$ 38.00
J.J. Tesla 12AX7A	3	$ 10.00	$ 30.00
NOS GE 12AT7 Phase Inverter	1	$ 11.00	$ 11.00
Electrolytic Caps			
100uf / 350v Sprague (Power Supply)	2	$ 6.00	$ 12.00
20uf / 500v Sprague (Power Supply)	3	$ 5.00	$ 15.00
25uf / 25v Sprague (Cathode Bias)	5	$ 1.50	$ 7.50
100uf / 100v Sprague (Bias Supply)	1	$ 3.00	$ 3.00
Signal Caps			
0.1uf /600v Orange Drop (Output Grid)	2	$ 1.50	$ 3.00
0.01uf /600v Orange Drop (Mix Tube In)	1	$ 1.00	$ 1.00
0.1uf /600v Orange Drop (Phase Input)	1	$ 1.50	$ 1.50
Resistors (2% Metal Film)			
1K, 4.7K and 27K ohm 1W (Power Supply)	3	$ 0.50	$ 1.50
470 ohm 1W (Screen)	2	$ 0.50	$ 1.00
1.5K ohm 1/2W (Output Grid)	2	$ 0.30	$ 0.60
Miscellaneous			
18g 3 prong 12ft power cord, ground eyelet and strain relief	1	$ 8.50	$ 8.50
Standby and on/off switches	2	$ 5.00	$ 10.00
2A Slow Blow Fuse	1	$ 0.75	$ 0.75
Parts Total			$ 144.35

Final Evaluation:

			Hrs Labor
Complete cleaning of chassis. Tighten all nuts, bolts, screws. Clean and lube all pots, jacks and switches. Clean and tighten all tube sockets, socket pins. Remove and clean rear faceplate.			1.5
Replace AC cord with new 3 prong cord			0.75
Perform a complete cap job			2
Replace grid and screen resistors			0.5
Replace output and interstage coupling caps			1
Replace Standby and on/off switches			0.25
Retube, set bias, burn in and voice amp			1
Final Test Results			
Completed:			
Total Labor (Hrs.)			7
Total Cost			
Parts:			$ 144.35
Labor: @ $25/hr			$ 175.00
Sub Total:			$ 319.35
Ship Amp Back to Customer:			$ 40.00
Total:			$ 359.35